Results of Actel RTAX-2000S Evaluation Test

Noriko Yamada <Yamada.noriko@jaxa.jp> Electronic, Mechanical Components, and Materials Engineering Group, JAXA

Nov. 27-29, 2007

MAFA Meeting





- JAXA has several plans to use Actel RTAX-2000S, which builds a large number of gates.
- Since the device has never been sufficiently evaluated for space applications.
- In 2005, we made a comprehensive antifuse evaluation of A54SX-S and RTSX-SU, devices of earlier generations and found some failure acceleration factor(voltage).





- Parts type: RTAX2000S-1CQ352E
- Test Samples: 3 pcs * 2 designs = 6 pcs
 - Lot: The same lot of the flight devices
- Measurements:
 - Functional test
 - DC test
 - Delay and Delta delay
 - 🏽 Fmax
- Designs: Two similar designs of the Flight Model
 - Target: Two designs from two JAXA projects



Programming and Screening

- Programming: Ver. 4.64 (for Windows)
- Electrical parameter test:
 - Group A subgroup 1,7,9 and Functional Test
- Burn-in test:
 - 125 °C 240 hours
 - Supply Voltage: $V_{CCA} = 1.6V$, $V_{CCI} = 3.5 \pm 0.2V$
- Final electrical parameter test (25 °C)
 - Group A subgroup 1,7,9 and Functional Test
 - Delta Delay
- Final electrical parameter test (maximum and minimum operating temperatures)
 - Group A subgroup 2,3,8,10,11



Results : Programming and Screening

Design	А	В
Visual inspection	3/3	3/3
Programming	3/3	3/3
Interim (pre burn-in) electrical parameters test	3/3	3/3
Burn-in test	3/3	3/3
Final electrical parameter test(25C)	3/3	3/3
Delta	3/3	3/3
Final electrical parameter test (Maximum and minimum operating temperature)	3/3	3/3

Pass/Test units

- Neither DC parameters nor AC parameters fluctuated in the electrical parameter tests. The both parameters were all within the speculation.
- Fmax fluctuation was 0.2MHz (t=0.31ns), which is not supposed to cause problems.



High Temperature Operating Life test (HTOL)

Test Condition

- Temperature: 125 °C
- Duration: 2000 hours
- Supply Voltage: $V_{CCA} = 1.6 \pm 0.1 V$, $V_{CCI} = 3.5 \pm 0.2 V$
- Operating Frequency: 0.25MHz
- Electrical Parameter Tests
 - Electrical parameter measurement
 - Delta
 - Measure period: 0H,240H,500H,1000H,1500H,2000H



Results : HTOL (1/3)



Nov. 27-29, 2007

MAFA Meeting



Results : HTOL (2/3)



Nov. 27-29, 2007

MAFA Meeting



Results : HTOL (3/3)



- For the both designs, measured DC parameters met the spec with an ample margin. The parameters did not fluctuate, remaining in the spec.
- AC parameters were also within the spec with an ample margin. The delta delays were from -0.4 to 0.2ns, while the delta delay spec is 10ns.





1/Fmax@3.6V



Α

Fmax fluctuation was 0.32MHz (t=0.2ns), which is not supposed to cause problems.

B





- After programming and screening test samples, we made a HTOL test.
- The test showed no failures in terms of DC, AC, functional test, delta delay and Fmax.
- This result suggests that the probability of malfunction will be very low, as far as we use devices of the same lot as ones used in this evaluation.
- We have established an evaluation methodology. We have already constructed DUT boards, BIBs, and so on. Now we are ready to evaluate and use the device.
- Since each FPGA application demands each level of quality and acceptable cost, we would like to upgrade our evaluation methodology so as to meet each project requirement in a cost-efficient manner.

